

## SP SERIES SELF-PRIMING PUMPS

### Stainless Steel Centrifugal Pumps

## SP Series

The SP Series self-priming centrifugal pumps are designed to be installed above the water line, providing a suction lift of 25' and offer a superior alternative to standard cast iron jet pumps.

The quality and performance you expect, along with industry best lead times and personalized service, only from Webtrol!



#### Features and Benefits

- 304 stainless steel pump
- Close coupled design
- Centerline discharge
- Non-overloading motor rated for continuous duty
- High operating efficiency
- Back pullout design for ease of servicing
- Mechanical seal for maximum reliability

#### Typical Services

- Home drinking water systems
- Deionized Systems
- Reverse Osmosis Systems
- Distribution Systems
- Misting Systems
- Car Wash Systems
- Liquid Transfer Systems
- Circulation Systems
- Pre-Filter Charge System
- Condensation Systems
- Cooling Tower Systems

#### Performance

HP Range: .75 & 1.5 HP, 60Hz


Capacities to 19 GPM

Pressures to 90 PSI

Temperatures to 113 °F

## SP Series

## SP SERIES FAMILY CURVES







There when you need us most


## SP SERIES GROUP CURVES

**SP**Series



## SP Series

## SP SERIES FAMILY CURVES Pump and Motor Dimensions



Model No.	Discharge / Suction/Imp. (inch-NPTF)	"A" Dimension	Single Phase Unit Weight (lbs.)		Three Phase Unit Weight (lbs.)	
			ODP	TEFC	ODP	TEFC
SPC75	1" x 1.25" x 4.5"	15.125"	37	41	39	43
SPC150	1" x 1.25" x 5.1875"	15.5625"	42	46	44	48

CONSTRUCTION MATERIALS	
Part	Material
Casing	304 SS
Impeller	304 SS
Shaft	Stainless Steel
Mechanical Seal	Carbon/Ceramic



## Webtrol's Family of Pumps

In addition to quality wastewater pumps, we also offer a full line of industrial and water well pumps.

The Webtrol industrial line includes vertical multistage booster pumps for commercial applications.

Our surface centrifugal and booster pumps include a wide range of self-priming,

corrosion resistant, high head, stainless steel, and cast iron pumps for a variety of industrial, commercial, and agricultural applications.

Our water well line includes 4", 6", 8", and 10" submersible stainless steel pumps.

See our full line of pumps and pump accessories at [webtrol.com](http://webtrol.com).



*There when you need us most*

**(314) 631-9200**

8417 New Hampshire Ave. | St. Louis, MO 63123  
[webtrol.com](http://webtrol.com) | [customerservice@webtrol.com](mailto:customerservice@webtrol.com) | Fax: (314) 631-3738

**WEBTROL** is a Division of Weber Industries, Inc.